

उत्तर बिहार ग्रामीण बैंक
प्रधान कार्यालय, कलमबाग चौक,
मुजफ्फरपुर, बिहार, 842 001



(Sponsored By :: Central Bank of India)

Uttar Bihar Gramin Bank

HEAD OFFICE, KALAMBAGH CHOWK,
MUZAFFARPUR, BIHAR, 842 001

☎ 2248141 Fax::(0621)2243088

Website :: www.ubgb.in

E-mail :: ubgb@ubgb.in, smgad@ubgb.in

Head Office

Tender No.GAD/08/2015-16/ 08

Date :: 11.08.2015

Tender Notice

Quotations for interior renovation, electrical, data cabling, UPS wiring work in New/existing branches/offices.

Uttar Bihar Gramin Bank invites competitive rates for interior renovation, electrical, data cabling, UPS wiring work at the proposed/existing branches/offices from empanelled vendors.

Terms & conditions.

Tenderers are advised to submit their rates in closed envelopes under following terms & conditions.

1. Quoted rates should be competitive.
2. If it is found that the material used is not same as mentioned in quotation then the Bank has the right to reject the work and for this Bank will not make any payment and the said firm will be removed from the Bank's empanelled list.
3. The lowest rates will be applicable for all vendors who will be interested to work.
4. If the work will be allotted to any vendor he should have to complete the job within stipulated time given by the Bank.
5. Rates quoted will be valid for one year.
6. Note that the measurement, quantity of different items are tentative and may increase/decrease as per the requirement of the Bank. The variation may be up to 20%.
7. After the allotted work is completed the work will be verified by Architect/ Branch Manager, Regional Manager.
8. Note that the Bank will not provide any advance against the work order.
9. Note that before starting the work material should be verified by Branch Manager/Regional Manager/Architect.
10. Vendors willing to work will have to deposit a fixed deposit receipt of Rs. 50,000/- to cover the defect liability. The FDR will be marked lien in favour of Bank for a period of 180 days. DLP will be one year from the date of installation.
11. If the vendor will get more orders then the FDR should be submitted with Head Office not less than 2% of total order value.
12. Quotations in a closed envelop should be submitted to **"The General Manager, Uttar Bihar Gramin Bank, Head Office, Muzaffarpur (842 001) on or before 19th Aug. 2015 up to 2.30 P.M.** The tenders submitted within the time will be opened on same day at 3.30 P.M. Bidders may remain present at the time of opening of bids.

[**R. K. RUNGTA**]
GENERAL MANAGER

**DETAILED SPECIFICATIONS FOR BILL OF QUANTITIES FOR INTERIOR WORKS FOR
UTTAR BIHAR GRAMIN BANK
MUZAFFARPUR HEAD OFFICE AT DIFFERENT BRANCHES**

SL.NO.	ITEM	PARTICULARS	QTY.	UNIT	RATE	AMOUNT
1	C.T.O. COUNTER	Providing & fixing 4'6"x2'6"x4'0" (Customer Side) x 2'6" (Inner Side) Height Making Computer counter with 19mm EXTERIOR GRADE MDF / water proof ply board (green / century make) finished with 1.0mm thick laminated (green / century make) with key board tray, CPU stand, poster frame , storing unite comprising of 3 drawer cabinet (Godrej/Mathodex make) cedar the table for security considering single window concept , telescopic slider, SS hardware, wire manager on all exposed surfaces finish & skarting etc. out of polished steamed beech/white cedar rubber wood with 12 mm. thick glass with etching in front. as per directions of bank / architect. The rate will include all the fitting & Excluding all taxes.	1	RFT.		
2	CASH COUNTER	Providing & fixing 4'6"x2'6"x4'0" (Customer Side) x 2'6" (Inner Side) Hite Making Computer counter with 19mm EXTERIOR GRADE MDF / water proof ply board (green / century make) finished with 1.0mm thick laminated (green / century make) with key board tray, CPU stand, poster frame , Cash storing unite comprising of 3 drawer cabinet (Godrej/Mathodex make) cedar the table for cash security considering single window concept , telescopic slider, SS hardware, wire manager on all exposed surfaces corlar finish & skarting etc. out of polished steamed beech/white cedar rubber wood. The front of the cash counter shall have 12mm glass with etching in two pieces with aluminium grill as per directions of bank/architect. The rate will include all the fitting & Excluding all taxes.	1	RFT.		
3	BRANCH MANAGER TABLE	Providing & fixing 6'0"x2'6" Making Computer table with beside storage 3'6"x1'3" with 19mm EXTERIOR GRADE MDF / water proof ply board (green / century make) finished with 1.0mm thick laminated (green / century make) with key board tray, CPU stand, storing unite comprising of 3 drawer cabinet (Godrej/Mathodex make) cedar the table , telescopic slider, SS hardware, wire manager on all exposed surfaces corlar finish & skarting etc. out of polished steamed beech/white cedar rubber wood. as per directions of bank / architect. The rate will include all the fitting & Excluding all taxes.	1	RFT.		
4	CASH CABIN PARTITION	Providing & fixing wooden partition 7' height comprising of both sides 9mm. Exterior Grade MDF / water proof ply board (green / century make) finished with 1.0mm thick laminated (green / century make) on the both sides approximate 3"x2" hardwood section 2'c/c both way laminate 1.0mm on the both side grooves to be made as per customized deginof bank / architect. The rate will include all the fitting & Excluding all taxes.	1	SFT.		
5	C.T.O. COUNTER PARTITION	Providing & fixing wooden partition 4' height comprising of both sides 9mm. EXTERIOR GRADE MDF / water proof ply board (green / century make) finished with 1.0mm thick laminated (green / century make) on the both sides approximate 3"x2" hardwood section 2'x2' both way laminate 1.0mm on the both side grooves to be made as per customized degin of bank / architect. The rate will include all the fitting & Excluding all taxes.	1	SFT.		
6	MANAGER CABIN PARTITION	Providing & fixing wooden partition 4' height comprising of both sides 9mm. EXTERIOR GRADE MDF / water proof ply board (green / century make) finished with 1.0mm thick laminated (green / century make) on the both sides approximate 3"x2" hardwood section 2'x2' both way laminate 1.0mm on the both side grooves to be made as per customized deginof bank / architect. The rate will include all the fitting & Excluding all taxes.	1	SFT.		

7	STORE/ UPS & PARTITION	Providing & fixing wooden partition up to ceiling Ht. comprising of both sides 9mm.EXTERIOR GRADE MDF / water proof ply board (green / century make) finished with 1.0mm thick laminated (green / century make) on the both sides approximate 3"x2" hardwood section 2"x2' both way laminate 1.0mm on the both side grooves to be made as per customized design of bank / architect. The rate will include all the fitting & Excluding all taxes.	1	SFT.		
8	OTHERS PARTITION	Providing & fixing wooden partition 4' high comprising of both sides 9mm. EXTERIOR GRADE MDF / water proof ply board (green / century make) finished with 1.0mm thick laminated (green / century make) on the both sides approximate 3"x2" hardwood section 2"x2' both way laminate 1.0mm on the both side grooves to be made as per customized design of bank / architect. The rate will include all the fitting & Excluding all taxes.	1	SFT.		
9	FALSE CEILING	Providing and fixing False ceiling in manager chamber and sarwar room False Ceiling which includes providing and fixing with ceiling angle of width 25mmx25mmx0.5mm thick to soffit with G.I. cleat and steel expansion fasteners.Ceiling section of 0.5mm thickness with 600mmx600mmx12mm Armstrong Make Beauty sky model false ceiling as per direction of Bank/architect.. The rate will include all the fitting. The rate will include all the fitting & Excluding all taxes.	1	SFT.		
10	MAIN DOOR & DOOR HANDLE	MAIN DOOR & DOOR HANDLE: Top & bottom approximate 83.5mm middle member thickness of section not less than 1.5mm Godrej/Dorma/Hafele/Ingersol Rand/Insta floor spring & pivot. On top 6mm clear glass with suitable rubber beading wool pipe/Weather strip on one vertical member providing & fixing customized door handle to fit on Aluminum Section. The rate will include all the fitting & Excluding all taxes.	1	SFT.		
11	NOTICE BOARD	Notice Board (Size 3'0"X2'6") The rate will include all the fitting & Excluding all taxes.	LUMSUM			
12	WRITING PAD	Writing Pad (Size 5'0") The rate will include all the fitting & Excluding all taxes.	LUMSUM			
13	PANNELLING	Paneling 2'X2' of sal wood fixed on the wall a distance of 1'-6"X1'-6" wooden frame and 6mm EXTERIOR GRADE MDF/water proof ply board pasted over it. The rate will include all the fitting & Excluding all taxes.	1	SFT.		
14	CHEQUE DROP BOX	Providing and fixing of Cheque Drop Box . The rate will include all the fitting & Excluding all taxes.	LUMSUM			
15	SUGGESTION BOX	Providing and fixing of Suggestion Box. The rate will include all the fitting & Excluding all taxes.	LUMSUM			
16	STORAGE	Providing & fixing 3'0"x1'6"x2'6" Making Storage cabinet with 19mm/12mm/10mm/6mm MDF / water proof ply board (green / century make) finished with 1.0mm thick laminated (green / century make) with unite comprising of 3 racks cabinet cedar the table , SS hardware on all exposed surfaces corlar finish & skirting etc. out of polished steamed beech/white cedar rubber wood. as per directions of bank / architect. The rate will include all the fitting & Excluding all taxes.	1	RFT.		
17	EMULSION PAINT	Providing & Applying three coats 1st Quality emulsion paint including scraping the surface clean with wall putti.The rate will include all the fitting & Excluding all taxes.	1	SFT.		
RS.				TOTAL		

CONTRACTOR'S SIGN. & SEAL

**DETAILED SPECIFICATIONS FOR BILL OF QUANTITIES FOR ELECTRICAL & LAN CABLING WORKS FOR
UTTAR BIHAR GRAMIN BANK
MUZAFFARPUR HEAD OFFICE AT DIFFERENT BRANCHES**

SL.NO.	ITEM	PARTICULARS	QTY.	UNIT	RATE	AMOUNT
1	2WAY MCB BOX	Providing and installation of 20A DP MCB all enclosed in a pre fabricated MS box of reputed manufacture complete in all respects including internal connections Havells/ Standred make.		SET.		
2	CHANGE OVER SWITCH	Supply & installation of 63Amp 415 volt. change over switch system to be installed on angle iron frame of proper size to be grouted on wall including interconnection in all respect Havells/ Standred make.		SET.		
3	M.S. COMPUTER BOARD	Supply and fixing computer socket cluster consisting of following components. [a] 3Nos. 5 Amp Switch [b] 3Nos. 3 pin Socket [c] 1 No. indicating lamp.		NOS.		
4	LIGHTS, FANS, CALL BELL, POWER POINTS, ETC. WIRING	Providing and making point wiring in walls, false ceiling, ceiling beams, furniture etc. with PVC conduits of 20 mm dia with bends, tees, elbows etc with 650v grade ISI Marked 2x1.5mm + 1x1.0mm sq for loop earthing PVC insulated copper conductor multi stranded flexible single cores wires with all accessories VIZ screws and washer 6A Piano type switches, fan regulators, 6A plugs and outlet boxes its accessories and button holder ceiling rose etc complete in all respects to the satisfaction of the employer Excluding the provision of circuit wiring with 3x2.5sq. Mm above PVC insulated copper wire.				
	A	One 6A switch controlling one light point		NOS.		
	B	5Amp. Socket outlet(3 pin) with 5Amp. SP switch as an independent point.		NOS.		
	C	One 6A switch controlling one fan point.		NOS.		
	D	Do- as item 1 but 5/15A(6pin) switch socket with out let boxes and 2x4.0sq mm + 1x2.5sq mm multi stranded single core PVC insulated copper conducted wire of 1100V grade and North West make accessories etc. complete in all respects from DB to 15A plug/socket point with controlling switch.		NOS.		
5	DISTRIBUTION BOARD	Supply, installation, testing and commissioning of factory assembled distribution board having in coming MCB as detailed below with natural link, suitable loop earth on 415v AC system and having overloaded as well as short circuit tripping elements with breaking capacity of 9KA to be installed on surface of the wall or concealed as per direction with transparent window cover complete with 200A copper bus bar and inter connections as required complete in all respects. Havells/ Standred make.				
	A	Computer DB (12 way MCB DB) Incoming :- SPN MCB 40 AMP.-01 Nos. Outgoing:- 6A to 32 Amp. SP MCB all complete set.		SET.		
6	WIRING	Supply & laying of undemoted size of PVC insulated flexible copper conductor wire Havells make in suitable size of recessed PVC conduit pipe including all connections etc. as required. Havells/ Fnolex make.				
	A	3X6.0Sq. Mm (For Incoming of UPS.)		MTR.		
	B	3X4.0Sq. Mm (For Outgoing of UPS & A.C. wiring)		MTR.		
	C	3X2.5Sq. Mm (For light circuit wiring)		MTR.		
	D	2X1.5Sq. Mm + 1X1.0Sq. Mm (For Computer Point wiring)		MTR.		
	E	1X8SWG (For Earth wiring)		MTR.		
7	LIGHTS	Supply & Fixing of light fixture				
	A	Call bell/bell with indicated including supply		NO.		
	B	Down light with 14watt LED Bulb include. All complete set. Havells/Philips		NOS.		
	C	Mirror optics AS series with 2x36 W FPL lamp Havells/Philips		NOS.		
8	CHEMICAL EARTHING	Maintenace free Chemical Earthing: Supply and installation based on earthing with inbuilt copper strip/GEL/GAF based. Should have resistance om and should be <2v between neutral and earth. Suitable electrode be used as per site requirements. Earth enhanced compound powder (Gel) with hardener to be provided minimum 20 Kg per site /Back Fill/site filled compound (BFC/BSC)-100Kg. Earthing warranty for 5 year. The electrode should be minimum 60 mm dia and 3 meter length or 80 mm dia and 2 meter length dedicated earthing.		NOS.		
9	KIT-KUT	Supply & fitting of 3Nos. 63Amp. Porcelien Kit-Kut on suitable size of wooden board including connections etc. as required.		SET.		
10	LAN CABLING	Wiring for LAN Switch Hub to terminal points with 1x8 Core Data networking CAT-6 PVC insulated copper cable in surface/ recessed rigid PVC conduit including connections etc. as required. D-Link.		MTR.		
11	I.O. BOX	Supply & fixing of IO Box controlling for terminal points complete in all connections etc. as required D-Link make.		NOS.		
12	PATCH COARD	Supply & fixing of Patch Coard D-Link make.		NOS.		
13	RJ-45	Supply & fixing of RJ-45 D-Link make.		NOS.		
RS.				TOTAL		0.00

CONTRACTOR'S SIGN. & SEAL