

उत्तर बिहार ग्रामीण बैंक
प्रधान कार्यालय, कलमबाग चौक,
मुजफ्फरपुर, बिहार, 842 001



(Sponsored By :: Central Bank of India)

Uttar Bihar Gramin Bank

HEAD OFFICE, KALAMBAGH CHOWK,
MUZAFFARPUR, BIHAR, 842 001

☎ 2248141 Fax::(0621)2243088

Website :: www.ubgb.in

E-mail :: ubgb@ubgb.in, smgad@ubgb.in

Head Office

Tender No.GAD/15/2022-23/1354

Date ::27.02.2023

Tender Notice
(Only empaneled Vendors can quote)

Uttar Bihar Gramin Bank invites competitive rates for interior renovation, electrical, LAN cabling, UPS wiring work at the proposed/existing branches/offices from empaneled vendors. Please submit your competitive rates in closed envelope positively on or before 14.03.2023 till 3.00 P.M. The financial bid will be opened on 14.03.2023 at Bank's Head office at 3.30 PM in presence of committee members. All empaneled vendors who submit rate quotes are requested to remain present at the time of opening of tender. Please note that no separate invitation will be sent.

Terms & conditions.

Tenderers are advised to submit their rates in closed envelopes under following terms & conditions.

1. Quoted rates should be competitive. All quoted rates should be exclusive of GST. GST is payable additionally as per prevailing rules. Bidders have to quote for all items mentioned in Annexures, **if the rate for any item is left blank, it will be treated as rejected.**
2. If it is found that the material used is not same as mentioned in quotation, then the Bank has the right to reject the work and for such work done Bank will not make any payment and the said firm will be removed from the Bank's empaneled list.
3. The L1 rate will be decided as per annexure attached separately. (Annx-I to Annx-VI)
4. The lowest rates will be applicable for all vendors who will be interested to work.
5. If the work is allotted to any vendor, he has to complete the job within stipulated/allocated time line given by the Bank.
6. Rates quoted will be valid for one year.
7. Please note that the measurement, quantity of different items are tentative and may increase/decrease as per the requirement of the Bank.
8. After the allotted work is completed the work will be verified by Architect/ Branch Manager, Regional Manager/ HO representative jointly.
9. Please note that Bank will not provide any advance against work order.
10. Please note that before starting the work, material should be got verified by Branch Manager/Regional Manager/Architect.
11. No additional packing, transportation, delivery or installation charge will be paid by the bank.
12. Financial Bid in a closed envelop should be submitted to **"The General Manager, Uttar Bihar Gramin Bank, Head Office, Muzaffarpur (842 001) on or before 14.03.2023 till 3.00 P.M.** The tenders submitted within the time will be opened on same day at 3.30 P.M. Bidders are requested to remain present at the time of opening of bids.
13. All work must be accomplished to the satisfaction of inspection committees comprising of Panel Architect, Branch Manager, Asst. Regional Manager/ Regional Manager and a staff from GAD

Head Office.


GENERAL MANAGER
HEAD OFFICE



UTTAR BIHAR GRAMIN BANK

Rate Quotes by Empanelled vendor only

Financial BID for CIVIL/ Renovation work

Annexure-I

L1 will be decided on individual section for Point 1 to 3

S.No.	Item/Description	Unit	Rate
1	FLOORING/ TILE WORK		
a	VITRIFIED TILES: Providing and laying of 600x600,8-10mm thick vitrified tiles excluding of skirting of make Somany/ Kajaria/ Orient laid on cement mortar (1 cement:5 coarse sand) including pointing of the joints with white cement and matching pigment complete as direct by Architect incharge.	Sq.ft	
b	VITRIFIED TILES SKIRTING: Providing and laying of 600x600,8-10mm thick vitrified tiles of 4" height of make Somany/ Kajaria/ Orient laid on cement mortar (1 cement:5 coarse sand) including pointing of the joints with white cement and matching pigment complete as direct by Architect incharge.	R.ft	
		Total	
2	PAINTING WORKS		
	PLASTIC EMULSION PAINT FOR WALLS & CEILING		
a	Providing and applying plastic emulsion paint(Nerolac/Asian/Dulux) for finish to walls, blocked partitions, and plasterboard, ceiling, etc of approved shade, texture. No cornices grooves pattas shall be measured separately. Only plane surface shall be considered for measurement. All works to be carried out as per manufacturers specification and guidelines.The surface of wall or ceiling to be painted shall be prepared to the satisfaction of the Architect, and shall be applied with two coats of primer, two coats of putty and touch up putty (Birla /JK) if required to achieve smooth finish. The surface shall be painted with two coats of Plastic emulsion paint . All rates inclusive of scaffolding and tools and tackles required for the same.	Sq.ft	
b	ENAMEL PAINT: Painting with synthetic enamel/ oil paint(Nerolac/Asian/Dulux) and colour to give and even shade in two or more coats as required/ directed. The cost includes making the surface smooth with oil based putty, red oxide paint in one coat in case of iron steel grill etc. complete after surface preparation rubbing cleaning complete. Door, Window, Grills, CG, Shutters.	Sq.ft	
c	Punning -This Item including providing and applying Plaster of Paris punning of required thickness existing wall & ceiling surfaces in true level and plumb complete as directed.	Sq.ft	
d	Oil paint to window & shutter – Thoroughly scraping and cleaning of surfaces and removing old loose flakes if any and apply over the same one coat of primer and two coat of Paint of approved brand as directed complete as per the direction of Consulting Engineer / in charge complete.	Sq.ft	



		Total	
3	Pelmet for fixing rolling / vertical blinds- made of 19mm commercial ply and palnt over it.	R.ft	
		Total	

- 1 Rates are quoted including all types of taxes, labour, material and transportation charges.
- 2 All quoted rates should be exclusive of GST.
- 3 Make of above items will be as per Annexure-A
- 4 Vendors who have been empanelled in the said category can apply for commercial Bid.

Authorized Signatories with seal

Name of firm:-

Date:-



UTTAR BIHAR GRAMIN BANK

Rate Quotes by Empanelled vendor only

Annexure-II

INTERIOR FURNISHING WORKS			Unit	Rate
S.No.	Item/Description			
1	FULL HEIGHT PARTITION/LOW HEIGHT PARTITION			
A	CONVENTIOAL TYPE	P/F SOLID PARTITIONS made out of Aluminium cross section (Size of section-2"x1.5")framework 2'-0" c/c both ways, covered with 6 mm thick commercial ply wood / partly glazed with approved shape & shade of 1mm thick laminate fixing on panel with 1.5 mm thick grooves in panel as per the design with provision of the openings in the panel for switch boards, box and cuts in frame for carrying conduits if necessary and fixing 1.0 mm laminate on the outside face of shade and colour as per Bank's colour scheme given in the tender specification with 8 mm glass to be given in the design if required. The open edges are to be blocked by teak wood beading with touchwood polish of required size and design. All provisions to be made for all electrical, networking boxes onto partition framework at required heights/levels with necessary additional supports as directed. PLY MAKE :- CENTURY (Sainik .) GREEN (Ecotec) Laminate Make :- GreenLam/ Century in 1mm Hardware Make :- GODREJ	Sq.ft	
B	MODULAR TYPE	P/F SOLID PARTITIONS made out of Aluminium cross section (Size of section-2"x1.5")framework 2'-0" c/c both ways, covered with 9X300 mm PVC Profile both side with self tapping screw corner pvc angles of shade and colour as per Bank's colour scheme given in the tender specification with 8 mm glass to be given in the design if require. The open edges are to be covered by 8mm Acrylic sheets nailed/ screwed in aluminium section and to be covered by silicon gel of required size and design. All provlions to be made for all electrical, networking boxes onto partition framework at required heights/levels with necessary additional supports as directed. PVC Profile MAKE :-Polywood, Rounaq,Duroplast	sq.ft	
2	SOLID FLUSH DOOR			
A	CONVENTIOAL TYPE	Providing and fixing Solid flush door made out of 35mm with both side laminate finish with necessary fitting with door closer provision . All material is of Green/Century make. Size of door 3'-0" x7'-0" Doors-Providing and fixing single leaf solid core flush door 35mm thick factory made, finished on both sides with 1.0mm thick laminate of approved shade as indicated in drawing. Shutter to be lipped on all sides with 12mm thick wooden beading. Applicable hardwares to be considered for following doors according to requirement as per detailed drawings including below mentioned hardware-Door closer,SS Ball bearing Hinges ,SS foot operated Door stopper,SS Mortise Latch Lock / concealed dead lock,SS Handle.Door closer and Mortice lock make-Godrej/link.	sq.ft	
B	MODULAR TYPE	Providing and fixing factory made PVC partitlons with frame of size 60x55mm, mitred at corners and joined welding the mitred ends, the profiles to be reinforced with 28x20mm M.S. sections of 2mm wall thickness, TPVrubber gasket weather seal should be coextruded with the profiles. The door frames and partitions to be fixed to the wall, ceiling and floor using 100mm nylon based anchors as per profile manufacturers specification.The mullions of dimensions 74mmx60mm with the profiles to be reinforced with 28x20mm M.S. sections of 2mm wall thickness and the large couplings of dimensions 86.2x43mm reinforced with 50x20mm MS sections of wall thickness 2.0mm.	sq.ft	
		The door shutter ---30mm thick door shutters made from 102mmx30mm PVC profiles coextruded with TPV gaskets and mitred ends which are welded together and reinforced with 50x30mm MS sections on all 4 sides. The prepared doors should be hung to the frame using 3/4 nos of 3D hinges depending on the door size and manufacturer's specifications. The doors should be lockable from both sides with multipoint locking systems including a non-locking spring latch operated by a door handle and a dead lock. Panels consist of 3mm ACP & / or color PVC profile 9x300 fixed both side with self tapping screw corner Pvc angle, glass 5 mm thick plain / etched as / design/ drawings (make atul, modifloat, gurind or equivalent) with all accessories including complete work as per direction of engineer in charge. with hardware & other items as necessary Including complete work. The Glass shall be 8 mm thick etched/ clear as / drawing including any other items needed for complete work as/ instructions & to the complete satisfaction of the inspection committee.		



3	TELLER COUNTER / CASH CABIN			
A	CONVENTIONAL TYPE	Providing and fixing top, front & side of cash counter made out of 18 mm commercial and termite proof blockboard as per design clad with 1.0 mm thick. Laminated on side and front & the edges to be finished with necessary white beach or white cedar lippings, mouldings, etc. 2'-6" wide working top made with 18mm blockboard with 1mm laminates. Special 16" drawer to be made for the cash with dividers of 12 mm commercial plywood the front of the drawer made out of 18mm blockboard finished with 1.0 mm laminate, sides 12 mm thick. commercial plywood and bottom to be made of 6 mm commercial plywood the inside and sides of the drawer to be duly polished. The drawers and shutters to be provided with necessary drawer sliding channels, hinges, locks etc. A leg rest to be provided made out of 18 mm thk. blockboard duly polished. Inside of the unit to be polished in the matching tone. All visible areas to be covered with beach or cedar lippings, mouldings with reddish brown colour polish. Wire manager, CPU trolley, keyboard tray to be provided. 4" ht. laminated skirting to be provided in all visible areas and 12 mm thick x 18" wide Plain Glass to be provided at counter top customer face horizontally at 3'-9" lvl. The work should be completed as per specification. Cost will be given by running feet measurement of front. All side partition will be paid separately.	RFT.	
B	MODULAR TYPE	Providing and fixing top, front & side of cash counter as modular partition with 2'-6" wide working top made with Table-top & Gables made of 25mm Pre-Lam Particle Board, Modesty Panels made using 17mm Pre-Lam Particle Board All visible edges would have POSTFORMED EDGING of semicircular profile. Keyboard tray to use full extension channels. Special 16" drawer to be made for the cash with dividers of 12 mm pre-laminated particle board. the front of the drawer made out of 18mm pre laminated particle board. The drawers and shutters to be provided with necessary drawer sliding channels, hinges, locks etc. A leg rest to be provided made out of 18 mm thk. blockboard duly polished. Wire manager, CPU trolley, keyboard tray to be provided. 12 mm thk. x 18" wide Plain Glass to be provided at counter top customer face horizontally at 3'-9" lvl. The work should be completed as per specification. Cost will be given by running feet measurement of front. All side partition will be paid separately.	RFT.	
4	C.T.O COUNTER			
A	CONVENTIONAL TYPE	Providing and fixing counters of size 4'-0"x2'-6" and the total height of 2'-6" as per detailed drawing, made up of 19mm board of CENTURY/ GREEN PLY and finished with 1 mm thick laminate of make and shade as approved, as per detailed drawing. Counter shall be provided with side drawers(1'-3" wide) sliding on telescopic channels (Ebco/ Godrej/Link make) and one storage below the drawer with proper locking arrangements and one keyboard with telescopic channels (Ebco/ Godrej make) . 12mm thick glass as a screen shall be provided in front, with a 3" gap from the counter top where required. Height of Glass: 18". Glass to be inserted in polished teakwood members, size 2" x 2", appropriately finished. The work includes providing and fixing of foot rests, shelf for CPU, furniture locks, wire managers, spirit polishing of steam beach/ white cedar beading etc. The inner exposed surfaces of table and drawers which are not visible by customers to be polished. All work complete in all respects to the entire satisfaction of the inspection committee.	RFT.	
B	MODULAR TYPE	Providing & fixing Tables with a depth of 4'-0"x 2'-6", Table-top & Gables made of 25mm Pre-Lam Particle Board, Modesty Panels made using 17mm Pre-Lam Particle Board , All visible edges would have POSTFORMED EDGING of semicircular profile Keyboard trays to use full-extension channels All table construction and carcass construction to be based on 15mm eccentric cam fittings All hardware should have an operational warranty of at-least 10 years Counter shall be provided with side drawers(1'-3" wide) sliding on telescopic channels (Ebco/ Godrej/Link make) and one storage below the drawer with proper locking arrangements and one keyboard with telescopic channels (Ebco/ Godrej make) . 12mm thick glass as a screen shall be provided in front, with a 3" gap from the counter top where required. Height of Glass: 18". The work includes providing and fixing of foot rests, shelf for CPU, furniture locks, wire manager etc. All work complete in all respects to the entire satisfaction of the inspection committee.	RFT.	
5	BRANCH MANAGER TABLE			
A	CONVENTIONAL TYPE	Providing and installing Table of size 5'-0"x2'-6"x2'-6" made up of 19mm of commercial board of CENTURY/ GREEN PLY and finished with 1 mm thick laminate of make and shade as approved, as per detailed drawing. Table shall be provided with side drawers(1'-3" wide) sliding on telescopic channels (Ebco/ Godrej/Link make) and one storage below the drawer with proper locking arrangements and a keyboard with telescopic channels (Ebco/ Godrej make) . The front modesty will be in 19mm of commercial board of CENTURY/ GREEN PLY and finished with 1 mm thick laminate of make and shade as approved, along with CPU trolley and a foot rest.	RFT.	



B	MODULAR TYPE	<p>Providing & fixing Tables with a depth of 5'-0" x 2'-6", Table-top & Gables made of 25mm Pre-Lam Particle Board, Modesty Panels made using 17mm Pre-Lam Particle Board , All visible edges would have POSTFORMED EDGING of semicircular profile</p> <p>Keyboard trays to use full-extension channels</p> <p>All table construction and carcass construction to be based on 15mm eccentric cam fittings</p> <p>All hardware should have an operational warranty of at-least 10 years</p> <p>Table shall be provided with side drawers(1'-3" wide) sliding on telescopic channels (Ebco/ Godrej/Link make) and one storage below the drawer with proper locking arrangements and one keyboard with telescopic channels (Ebco/ Godrej make) . The work includes providing and fixing of foot rests, shelf for CPU, furniture locks, wire manager etc.All work complete in all respects to the entire satisfaction of the Inspection committee.</p>	RFT.	
6 WALL CLADDING/ PANELING FOR WALL AND COLUMNS				
A	CONVENTIONAL TYPE	<p>P/F wall paneling made out of Aluminium cross section 2"x1" section framework 2'-0" c/c both ways, covered with 6 mm commercial ply of Green/ Century make and 1mm laminates with 1mm groove patterns with skirtings as per banks design. All provisions to be made for all electrical, networking boxes onto partition framework at required heights/levels with necessary additional supports as directed.</p>	Sq.ft	
B	MODULAR TYPE	<p>Providing, fitting and fixing extruded Aluminium box section 1.5" x1" framing vertically and horizontally with jointing cleat angle, PVC fastener and m.s. screw with 3mm thick aluminum composite panel(ACP) of approved color (make Alstone/GuruInd/Alupan) & ACP joint best quality silicon for proper jointing with label all complete as per diction of Engineer Incharge/ Bank.</p>	Sq.ft	
7 SIDE CREDENZA/ STORAGE UNIT (Front area to be measured)				
A	CONVENTIONAL TYPE	<p>Providing & fixing storage units made up 18 mm. thk. plywood framework, 6 mm. thk. plywood back as required as per design. Good quality blockboard shutters should be fixed on SS heavy hinges Storage units. should be finished with 1.0 mm. thk. laminate from external side & oil paint to non laminated surfaces. All exposed edges of plywood should have lipping patti on it. The cost should include necessary handles, magnetic catches, Godrej make locks etc. complete as per design.</p>	Sq.ft	



B	MODULAR TYPE	The Credenza should have a depth of 450mm and each credenza for each staff should have 3 lockable drawers and 1 shutter Top of Credenza 25mm Postformed Particle Board ,Cabinets & drawers made using 17mm & 9mm Pre-Lam Particle Board. All internal edges would have 0.45mm thick Edge-banding. All visible edge should have 25mm dia semicircular post formed profile. All edge-banding to be machine pasted using Hot-melt glue of Pidllite. All drawers to use full-extension telescopic channels. all carcass construction to be based on 15mm eccentric cam fittings. All hardware should have an operational warranty of at-least 10 years.	Sq.ft	
8	FROSTED FILM and BANK LOGO	Providing and pasting frosted film (3M, Garware make) on glass work including Bank's logo as required & as directed by the committee.	Sq.ft	
9	CHEQUE DROP BOX :(1'-3" x 1'-6"X 10" deep)			
A	CONVENTIOAL TYPE	Providing and fixing cheque drop boxes made out of 19mm thick. Commercial plywood finished with 1mm thk. Laminate. Slit/s should be provided to drop cheques and opening provided with locking arrangement to remove cheques, complete in all respect.	NOS.	
B	MODULAR TYPE	Providing and fixing cheque drop boxes made out of 19mm thick. Pre laminated board. All internal edges would have 0.45mm thick Edge-banding. Top visible edge should have 25mm dia semicircular post formed profile. Slit/s should be provided to drop cheques and opening provided with locking arrangement to remove cheques, complete in all respect.	NOS.	
10	NOTICE BOARD:	Providing and fixing notice board of 4'-0"X2'-6" size in ply board of 6mm fixed with aluminium beading all sides. 12mm thick. Soft board clad with fabric of matching colour and shade complete with all fixtures necessary as required	NOS.	
11	WRITING DESK	Writing desk made of 19mm plyboard/ Pre laminated board fixed on wall as per Design Size: 3'0"X1'0" minimum. Writing Ledge to have facility of pigeon holes beneath to place the pay in / payout slits etc. Size of pigeon holes- 5"x5"	NOS.	
12	FALSE CEILING			
	a	PLAIN GYPBOARD FALSE CEILING WITH PAINTING : Providing and fixing suspended false ceiling consisting of 12.5mm thick Gypsum board (India Gypsum/Armstrong/ Saint Gobin) suspended on GI framework. GI framework to consist of GI perimeter channels 0.55mm thick 20mm x 30mm along perimeter of false ceiling , screw fixed to wall/partition with nylon sleeves and screws @ 600mm c/c. Suspending GI intermediate channels of size 0.9mm thick 45mm x 15mm from the soffit at max dist 1220mm c/c with ceiling angle 0.55mm thick 25mm x 10mm fixed to soffit using proprietary supplied GI cleats and steel expansion fasteners.Boards to be finished with proprietary supplied jointing tape and jointing compound and sand papered to achieve a smooth and seamless finish and 2 coats of primer alongwith coats of Acrylic paint suitable for Gypsum board upto Bank's Satisfaction .Rate quoted to include vertical all cut-outs required for light fixtures, smoke detectors and other services cut-outs complete as directed committee.	Sq.ft	
	b	GRID FALSE CEILING /Modular False ceiling :Providing and fixing suspended false ceiling consisting : approved make MODULAR CEILING India Gypsum/Armstrong/ Saint Gobin		
		Suspension system of False ceiling will be measured on horizontal plane only. Horizontal plane measurements are to be inclusive of all vertical drops, edge mouldings, fascias, etc.Rate quoted to include all cut-outs required for light fixtures, smoke detectors and other services cut-outs complete as directed by Architect. Rate quoted to include cost of providing support framework formed of perimeter channels for fixing light fixtures, AC grills/diffusers etc. Also to provide concealed perimeter channel support as required to support modular grid ceiling sections at junction between gypboard false ceiling and modular grid tile ceiling	Sq.ft	
13	Vertical blinds	P/F Blinds made using 100% polyester with acrylic polymer coating.(only for external windows. In case of front facia necessary approval need to be obtained)	Sq.ft	

- 1 L1 Rates will be decided on the basis of (1A,2A to 13) for conventional work and (1B, 2B to 13) for modular work separately.
- 2 Rates are quoted including all types of taxes, labour, material and transportation charges.
- 3 All quoted rates should be exclusive of GST.
- 4 Make of above items will be as per Annexure-A
- 5 Vendors who have been empanelled in the said category can apply for commercial Bid.

Authorized Signatories with seal

Name of firm:-

Date:-



UTTAR BIHAR GRAMIN BANK

Rate Quotes by Empanelled vendor only

Financial BID for CIVIL/ Renovation work- Electric Items

Annexure-III

L1 rates will be decided on sum of Point 1 to 4

Sl no	Providing & Fixing of following Lighting Fixtures and Fittings as described :	Unit	Rate
1	Supply ,testing and commissioning of 2x2 recessed Light Type 36 watt fixtures complete with all accessories as required.	Nos	
2	Supply ,testing and commissioning of 12 W Down lighter Light fixtures complete with all accessories as required.	Nos	
3	LED Tube lights 4"	Nos	
4	LED Bulb 12watt		
		Total	

- 1 Rates are quoted including all types of taxes, labour, material and transportation charges.
- 2 All quoted rates should be exclusive of GST.
- 3 Make of above items will be as per Annexure-A
- 4 Vendors who have been empanelled in the said category can apply for commercial Bid.

Authorized Signatories with seal

Name of firm:-

Date:-



UTTAR BIHAR GRAMIN BANK

Rate Quotes by Empanelled vendor only

Financial BID for Renovation work-Electric work

Annexure-IV

L1 rates will be decided on sum of Point 1 to 16

SR NO	DESCRIPTION	UNIT	Rate
1	MAIN ELECTRICAL Cubical type panel.		
	Supply, erection, connecting, testing and commissioning of cubicle type panel fabricated out of CRCA sheet teel , Wall mounted totally enclosed switchbaord of uniform width sutable for use of 415 volts , 3 phase, 50 HZ complete and housed with Copper bus bar equipments and their accessories including supply and fixing of base channel of 100 x 50 x 6 mm as required and with following incoming and outgoing switchgear as per the specifications and schematic diagram Powder Coated.		
	Size of panel -- 39"X30"X12"(LXWXD)		
	INCOMER:		
	1 Nos 63A TPN,25kA, MCCB's with microprocessor based releases for overcurrent, shortcircuit and earth fault, with isolable neutral ,ON indication, 1 no. multifunction digital meter (showing all power parameters), with selector switch, matching cast resin CT's.		
	63A 100 ma RCCB 4POLE	nos	
	BUS BAR		
	A set of TPN Copper bus bar rated for 125A (after considering all necessary deratings) 3 phase 4wire, 50Hz. For main Line.		
	A set of TPN Copper bus bar rated for 100A (after considering all necessary deratings) 3 phase 4wire, 50Hz. For DG Set.		
	(All Internal Wiring With 16 Sq. mm copper Wire)		
	OUTGOING		
	1 nos 40 A TPN MCB's, 10 kA with indication lamps		
	3 nos 40 A DP MCB's, 10 kA with indication lamps		
	1 nos 16/20 A DP MCB's, 10 kA with indication lamps		
	Other Items such as		
	1 Lot of control Copper wiring		
	1 Set of designation plates		
	with all internal wirring and thimble including.		
	Including 63 A three phase manual changeover switch		
	MEDIUM VOLTAGE SWITCHGEAR & DISTRIBUTION BOARDS:		
2	4Way TPN DB for Power & Lighting -Supplying & installation 4way TPN DB Legrand/ABB/ L&T make	Nos	
3	12 Way SPN DB for UPS -Supplying & installation 12 way SPN DB of Legrand/ABB/ L&T make	Nos	
4	63 / 40 Amp TPN MCB with MS Enclosure.	Nos	
5	25 / 32 Amp TPN MCB with MS Enclosure.	Nos	
6	25/32 Amp DP MCB with MS Enclosure	Nos	
7	6/10 SP MCB	Nos	
	MEDIUM VOLTAGE CABLING:		
8	Providing and Laying of 1.1. KV PVC Insulated Armoured Cables as described under :		
a	4C x 10 Sq.mm. Aluminium Armoured Cable	Mtr	
b	3.5 C x 35 sq.mm. at 1100 volts grade PVC Insulated aluminum conductor armored cable	Mtr	
9	Cable Termination as described under with Single Compression Gland :		
	4C x 10 Sq.mm. A2XWY	Nos	
	CONDUIT WIRING:		
10	Wiring Light Point with 3 Nos x 1.5 Sqmm Cu. Wire In PVC LMS Pipe controlled by 6 Amp Switches as described below :		
a)	Primary Light Point.	Point	
b)	Secondary Light Point.	Point	



c)	6 Amp RAW POWER Plug Point on Switch Board with 6 Amp Switch + 6 Amp Universal Socket Outlet	Point	
d)	Wiring Ceiling Fan Point with Fan Regulator.	Point	
9	Wiring Long Point circuit 2 x 1.5 sq.mm. wire with 1.5 sq.mm. earthing wire in PVC LMS Pipe from LDB to Switch board.	Mtr	
10	Wiring Lighting circuit 2 x 2.5 sq.mm. wire with 1.5 sq.mm. earthing wire in PVC LMS Pipe from LDB to Switch board.	Mtr	
11	Wiring Power circuit 2 x 4.0 sq.mm. wire with 1.5 sq.mm. earthing wire in PVC LMS Pipe from PDB to A/C & Power Plug Point.	Mtr	
12	Providing and Fixing of 6/16 Amp Switch – Socket with Plate and Box for Power Point.	Nos	
13	Providing and Fixing of 2 Nos. 6 Amp Switch + 2 Nos 6 Amp Universal Socket with Plate & Box for UPS.	Nos	
14	Providing and Fixing of 1 No 6 Amp Switch + 1 No. 6 Amp Universal Socket with Plate & Box for Raw power	Nos	
15	Wiring Long Point circuit 2 x 1.5 sq.mm. wire with 1.5 sq.mm. earthing wire in PVC LMS Pipe from LDB to workstation .	Mtr	
16	Wiring Lighting circuit 2 x 2.5 sq.mm. wire with 1.5 sq.mm. earthing wire in PVC LMS Pipe from LDB to workstation .	Mtr	

- 1 Rates are quoted including all types of taxes, labour, material and transportation charges.
- 2 All quoted rates should be exclusive of GST.
- 3 Make of above items will be as per Annexure-A
- 4 Vendors who have been empanelled in the said category can apply for commercial Bid.

Authorized Signatories with seal

Name of firm:-

Date:-



UTTAR BIHAR GRAMIN BANK

Rate Quotes by Empanelled vendor only

Financial BID for Renovation work-Electric Earthing work

Annexure-V

L1 rates will be decided on sum of Point 1 to 3

B.O.Q. for Rural Branch (ELECTRICAL WORK PART-I)

SR NO	DESCRIPTION	UNIT	Rate
EARTHING SYSTEM:			
1	Providing & Fixing of GI Chemical Earthing with following specifications :	Nos	
	Electrode Diameter: 50mm		
	Electrode Length: 3000mm		
	Thickness: 0.254mm		
	Internal Strip Size: 40 x 6mm		
	Connection Terminal Die: 14 x 2mm		
	Material of Construction: GI Boned		
	Compound Filled: Crystalline Mixture		
	Earthing Chamber - 1 No		
2	Providing & Fixing of Copper Chemical Earthing with following specifications :		
	Electrode Diameter: 50mm		
	Electrode Length: 3000mm		
	Thickness: 0.254mm		
	Internal Strip Size: 40 x 6mm		
	Connection Terminal Die: 14 x 2mm		
	Material of Construction: Copper Boned		
	Compound Filled: Crystalline Mixture		
	Earthing Chamber - 1 No		
3	Providing and Laying of 4sq.mm. Copper Insulated Earthing wire with conducting	Mtr	
		Total	

- 1 Rates are quoted including all types of taxes, labour, material and transportation charges.
- 2 All quoted rates should be exclusive of GST.
- 3 Make of above items will be as per Annexure-A
- 4 Vendors who have been empanelled in the said category can apply for commercial Bid.

Authorized Signatories with seal

Name of firm:-

Date:-



UTTAR BIHAR GRAMIN BANK

Rate Quotes by Empanelled vendor only

Financial BID for Renovation work-Data/LAN cabling

Annexure-VI

L1 rates will be decided on sum of Point 1 to 7

SR NO	DESCRIPTION	UNIT	Rate
	B)DATA CABELING WORKS		
	ITEM AND SPECIFICATION		
	COMPUTER CABLING SYSTEM.		
	COMPUTER POINT : I / O's :		
	Supplying, Installation, testing and commissioning of the Computer point with the followings -		
	Four pair UTP CAT 6 LAN cable tinned copper conductor, P.V.C. insulated and sheathed , fire retarding, anti termite, color coded twisted pairs and rip cord in 25 mm dia MMS PVC conduit		
1	Single outlet with shutter modular type I / O's Outlets (RJ - 45) with suitable size PVC modular boxes complete inclusive telephone cable and conduit	NOS	
	Supply and Installation of following factory fabricated patch cords (UTP-CAT 6) complete with connectors and boots on both sides.		
2	Two Meter length	NOS	
3	Supply and laying of UTP-CAT 6 LAN cables including cost of 25mm dia 1.5mm thick PVC Conduit / Floor trunking.(Rate Only)	MTR	
	Supplying and fixing		
4	4U Rack 3 side open	NOS	
5	16 Port rack mountable Switch	NOS	
6	16-Port Cat6 Unshielded Wallmount or Rackmount Patch Panel,	NOS	
7	Patch cord cat6 (1 metre B/Y Color)	NOS	
	Total		

- 1 Rates are quoted including all types of taxes, labour, material and transportation charges.
- 2 All quoted rates should be exclusive of GST.
- 3 Make of above items will be as per Annexure-A
- 4 Vendors who have been empanelled in the said category can apply for commercial Bid.

Authorized Signatories with seal

Name of firm:-

Date:-



UTTAR BIHAR GRAMIN BANK		
Annex-A		
INTERIOR MAKE LIST		
1	Ply Board	Century/ Green
2	Block Board	Century/ Green
3	Laminates	Greenlam / Century / Sunmica
4	Door Closer	Godrej/Link/Quba
5	Door/Drawer Handle	Godrej/Link/Quba
6	Telescopic channels	Godrej/Link/Quba
7	Magnet/ Tower Bolt	Godrej/Link/Quba
8	Locks	Godrej/Link/Quba
9	Floor Spring	Ozone/ HARDWIN/Godrej
10	Toughened Glass	Saint Gobin/ Modi Guard/Ais
11	Plain Glass	Saint Gobin/ Modi Guard/Ais
12	Grid Type False Ceiling	India Gypsum/Armstrong/ Saint Gobin
13	Gypsum False Ceiling	India Gypsum/Armstrong/ Saint Gobin
14	Vertical Blinds	MARVEL / VISTA/ad
15	Paints	Asian/Nerolac
16	Glue	Fevicol

ELECTRICAL MAKE LIST		
1	Wire	HAVELLS /FINOLEX/POLYCAB
2	Switch, Socket	LEGRAND /ROMA/HAVELLS/ L&T
3	Ceiling fan	Crompton/Havells/Usha
4	Wall fan	Crompton/Havells/Usha
5	Exhaust fan	Crompton/Havells/Usha
6	18W round light	Syska/Havells/Magik
7	2'X2' Square light	Syska/Havells/Magik
8	Armoured cable	Finolex/Havells/Polycab
9	Earthing	Remedies/Ashlok
10	MCB/MCCB/DB	LEGRAND/ABB/SCHNEIDER/L & T/ SIEMENS
11	AC Socket	Phillips/Havells/Anchor
12	10W LED light	Syska/Havells/Magik
13	PVC pipe	Durga/Malhotra/ANCHOR – ISI MARKED

